Number: SOP-REACTOR-STARTUP	Use Category: CONTINUOUS	Major Rev: 003
Title: Reactor Startup		Minor Rev: 001 Page: 1 of 7

TABLE OF CONTENTS

	IABLE OF CONTENTS	
1.0 2	Mode 3	<u>Page</u>
2.0	Mode 2	
3.0	Heating Range	4
4.0 5	Mode 1	
	TABLES AND FIGURES	
Table	1.1, Commonly Used Acronyms	6

Number: SOP-REACTOR-STARTUP	Use Category: CONTINUOUS	Major Rev: 003
Title: Reactor Startup		Minor Rev: 001 Page: 2 of 7

1.0 *MODE 3*

NOTE:

The following groups of steps should be performed concurrently, except for 1.4, which may be performed after every step has been completed.

1.1 <u>ADMIN</u>

- 1.1.1 **VERIFY** all personnel out of the drywell **PRIOR** to placing the mode switch in START/HOT STBY
- 1.1.2 **PRIOR** to switching to Mode 2, **VERIFY** RPS trip systems restored to service per SOP-RPS-BYPASS
- 1.1.3 **OBTAIN** permission from the Operations Manager to place the Mode Switch in the START/HOT STBY position.
- 1.1.4 **CONDUCT** a panel walk down looking for equipment status that may not be consistent with Mode 2 operation.
- 1.1.5 **VERIFY** reactor scram reset.

1.2 NSS/BOP/POWER

- 1.2.1 **OPEN** the MSIVs per SOP-MSIV-OPS
- 1.2.2 **SECURE** Shutdown Cooling per SOP-RHR-SDC
- 1.2.3 **VERIFY** RHR is in a standby lineup per SOP-RHR-STBY
- 1.2.4 **VERIFY** both RRC pumps are running at 15 Hz per SOP-RRC-START
- 1.2.5 **VERIFY** RCIC-V-13 Closed.
- 1.2.6 PRIOR to 48 psig, **VERIFY** the following are closed;
 - RHR-V-8
 - RHR-V-9
- 1.2.7 **VERIFY** LPCS lineups completed, SOP-LPCS-STBY.

Number: SOP-REACTOR-STARTUP	Use Category: CONTINUOUS	Major Rev: 003
Title: Reactor Startup		Minor Rev: 001 Page: 3 of 7

- 1.2.8 **START** CRD per SOP-CRD-STARTUP.
- 1.3 LEVEL
 - 1.3.1 LINEUP RWCU for blowdown, in accordance with SOP-RWCU-OPS
 - 1.3.2 PREPARE RFW for level control, SOP-RFW-STARTUP.
 - 1.3.3 **VERIFY** HPCS lineups completed, SOP-HPCS-STBY.
- 1.4 **PLACE** the Mode Switch in the START/HOT STBY position.
- 2.0 MODE 2

NOTE:

The following groups of steps should be performed concurrently.

2.1 LOG The time and date of entry into Mode 2. Time_____ Date____

- 2.2 POWER
 - 2.1.1 **PERFORM** SOP-RWM-STBY.
 - 2.1.2 WITHDRAW the 1st control rod as directed by the rod worth minimizer pull checklist.

NOTE:

The following step may not be performed if the reactor is being started up with the RWM inoperable (LCO 3.3.2.1 C).

- 2.1.3 <u>WHEN</u> the 1st control rod is withdrawn to its target position, <u>THEN</u> **PERFORM** OSP-RWM-C401.
- 2.1.4 **WITHDRAW** control rods as directed by the rod withdrawal sequence sheet to achieve criticality.

Number: SOP-REACTOR-STARTUP	Use Category: CONTINUOUS	Major Rev: 003
Title: Reactor Startup		Minor Rev: 001 Page: 4 of 7

2.2 POWER (cont)

- 2.1.5 **MAINTAIN** Reactor Period GT 60 seconds.
- 2.1.6 <u>WHEN</u> neutron level rises, <u>THEN</u> **VERIFY** IRM response.
- 2.1.7 **WITHDRAW** SRMs to maintain indicate levels between the rod blocks. (100 cps and 1X10E5 cps)
- 2.1.8 **ADVANCE** the IRM range change switches to maintain an indication of 25 to 75.

2.3 LEVEL/NSS/BOP

- 2.2.1 **PERFORM** Prestart checks on the first Reactor Feed Pump.
- 2.2.2 With RPV pressure below the RCIC isolation limit,

 BEGIN SOP-RCIC-STBY with those steps which can be performed.
- 2.2.3 **PERFORM** Prestart checks on the second Reactor Feed Pump.

3.0 HEATING RANGE

NOTE:

The following groups of steps should be performed concurrently.

3.1 NSS/BOP

NOTE:

RCIC should be made operable prior to 150 psig (LCO 3.5.3)

- 3.1.1 WHEN RPV pressure increases to 68 psig, CONTINUE SOP-RCIC-STBY.
- 3.2 POWER

Num	ber: SO	P-REA	CTOR-STARTUP	Use Category: CONTI	NUOUS	Major Rev: 003
Title: Reactor Startup					Minor Rev: 001 Page: 5 of 7	
	3.2		VERIFY APRMs response. R (cont)			
		3.2.2	MAINTAIN power be	elow the APRM rod bloo	ck (12%).	
block.		3.2.3 WITHDRAW IRMs as required to maintain indications below the rod			elow the rod	
	3.3	PRES:	<u>SURE</u>			
		3.3.1	MAINTAIN 100°F/hi modulating the EHC	r with the Main Turbine look pressure setpoint.	Bypass Valv	es by
		3.3.2	VERIFY Bypass val to the EHC setpoint	ve opens when pressur	e increases	
	3.4	<u>LEVEL</u>	<u>-</u>			
		3.4.1	CONTINUE SOP-R	FW-STARTUP as key p	arameters a	re reached.
	3.5	AND A	Reactor Power is GE III MSIVs are open,	s greater than 850 psig, 5%, Mode Switch in the RUI	N position.	
4.0	MODE	<u>. 1</u>				
	4.1	LOG T	The time and date of	entry into Mode 1.	Time	Date
	4.2	INCRE	ASE Reactor Power	to 20%.		
	4.3	BEGIN placing the Main Turbine on-line, per SOP-MT-STARTUP.				

 $\underline{\text{WHEN}}$ The Main Turbine has been placed on-line,

THEN INCREASE Reactor Power to 100%, not exceeding 10 MWE per minute.

4.4

Number: SOP-REACTOR-STARTUP	Use Category: CONTINUOUS	Major Rev: 003
Title: Reactor Startup		Minor Rev: 001 Page: 6 of 7

TABLE 1.1, Commonly used acronyms

"RRC"	Reactor Recirculation Control
"RPS"	Reactor Protection System
"BISI"	Bypass Inoperable Status Display
"RHR"	Residual Heat Removal
"HPCS"	High Pressure Core Spray
"LPCS"	Low Pressure Core Spray
"RCIC"	Reactor Core Isolation Cooling
"RFW"/"RFP"/"RFT"	Reactor Feed Water/Pump/Turbine
"RPV"	Reactor Pressure Vessel
"RX"	Reactor
"P601"	Panel 601 (Panel numbers listed with white label on top of each panel)
"P602"	Panel 602 (See "P601")
"P603"	Panel 603 (See "P601")
"P800"	Panel 800 (See "P601")
"P820"	Panel 820 (See "P601")
"P840"	Panel 840 (See "P601")
"RWM"	Rod Worth Minimizer
"MSIV"	Main Steam Isolation Valve (P601)
"APRM"	Average Power Range Monitor
"IRM"	Intermediate Range Montior
"SRM"	Source Range Monitor
"MS"	Main Steam

Number: SOP-REACTOR-STARTUP	Use Category: CONTINUOUS	Major Rev: 003
Title: Reactor Startup		Minor Rev: 001 Page: 7 of 7

"COND"	Condensate System
"MLB"	Million Pounds
"GE"	General Electric OR Greater Than or Equal To
"LE"	Less Than or Equal To
"GT"	Greater Than
"LT"	Less Than