| Number: SOP-RFW-STARTUP                 | Use Category: CONTINUOUS | Major Rev: 003                  |
|---|--------------------------|---------------------------------|
| Title: Reactor Feedwater System Startup |                          | Minor Rev: 001<br>Page: 1 of 27 |

- 1.0 <u>FEED SYSTEM STATUS DETERMINATION</u>
- 1.1 **START** RFT-P-MOPA(B)
- 1.2 **VERIFY** RFT Control and Trip oil at 100-130 psig
- 1.3 **VERIFY** RFT Lubricating oil at 15-20 psig
- 1.4 **START** RFT-P-AOPA(B)
- 1.5 **STOP** RFT-P-MOPA(B) and **REPEAT** steps 1.2, 1.3
- 1.6 **VERIFY** no unexplained annunciators in for each RFT
- 1.7 <u>IF RPV Pressure is less than 300 psig OR</u> any previous step failed, <u>THEN</u> **ENTER** 4.0 of this procedure
- 1.8 <u>IF RPV Pressure is GE 300 psig,</u> <u>THEN</u> **ENTER** 2.0 of this procedure

| Number: SOP-RFW-STARTUP                 | Use Category: CONTINUOUS | Major Rev: 003                  |
|---|--------------------------|---------------------------------|
| Title: Reactor Feedwater System Startup |                          | Minor Rev: 001<br>Page: 2 of 27 |

## 2.0 RFT A STARTUP

- 2.1 **START** RFT-P-MOPA
- 2.2 **STOP** RFT-P-AOPA
- 2.3 **VERIFY** Control and Trip oil at 100-130 psig
- 2.4 **VERIFY** Lubricating oil at 15-20 psig
- 2.5 **RESET** RFW-DT-1A Turbine Trip
- 2.6 OPEN MS-V-105A "HP STEAM SUPPLY"
- 2.7 <u>WHEN RPV Pressure is GT 400 psig,</u>
  - 1. OPEN RFW-V-102A "PUMP A DISCHARGE"
  - 2. CLOSE COND-V-149 "COND PUMP STARTUP BYPASS"
- 2.8 <u>WHEN RPV Pressure is GT 500 psig,</u> <u>THEN ENTER</u> 3.0 of this procedure.

| Number: SOP-RFW-STARTUP                 | Use Category: CONTINUOUS | Major Rev: 003                  |
|---|--------------------------|---------------------------------|
| Title: Reactor Feedwater System Startup |                          | Minor Rev: 001<br>Page: 3 of 27 |

- 3.0 RFT B STARTUP
- 2.1 **START** RFT-P-MOPB
- 2.2 **STOP** RFT-P-AOPB
- 2.3 **VERIFY** Control and Trip oil at 100-130 psig
- 2.4 **VERIFY** Lubricating oil at 15-20 psig
- 2.5 **RESET** RFW-DT-1B Turbine Trip
- 2.6 **OPEN** MS-V-105B "HP STEAM SUPPLY"
- 2.7 **OPEN** RFW-V-102B "PUMP A DISCHARGE"
- 2.8 <u>IF</u> all RFTs are started, <u>THEN</u> **ENTER** 5.0 of this procedure.

| Number: SOP-RFW-STARTUP                 | Use Category: CONTINUOUS | Major Rev: 003                  |
|---|--------------------------|---------------------------------|
| Title: Reactor Feedwater System Startup |                          | Minor Rev: 001<br>Page: 4 of 27 |

## 4.0 INJECTION WITH CONDENSATE PUMPS

## **CAUTION**

At very low flows, the startup level controller may oscillate due to the feedback signals being very weak. The startup level controller may **NOT** properly maintain level in the AUTO mode until approximately 5% demand signal.

- 4.1 **START** the Condensate Booster Pumps, (P820)
  - COND-P-2A
  - COND-P-2B
  - COND-P-2C
- 4.2 **INJECT** feedwater from the condensate booster pumps. (P840)
  - 1. OPEN COND-V-149 "COND PUMP START UP BYPASS"
  - 2. OPEN RFW-V-117A/B "FEEDWATER CLEANUP/ STARTUP VALVE"
  - 3. OPEN RFW-V-118 "FEEDWATER STARTUP ISOLATION"
  - 4. OPEN RFW-V-65A/B "REACTOR FEEDWATER LOOP VALVE A(B)"
  - 5. **PLACE** the startup level controller in AUTO
- 4.3 <u>WAIT</u> for reactor pressure to become GE 300 psig, THEN **ENTER** section 2.0 of this procedure.

| Number: SOP-RFW-STARTUP                 | Use Category: CONTINUOUS | Major Rev: 003                  |
|---|--------------------------|---------------------------------|
| Title: Reactor Feedwater System Startup |                          | Minor Rev: 001<br>Page: 5 of 27 |

## 5.0 TRANSFER FEED SYSTEM TO MASTER CONTROLLER

<u>CAUTION</u> Due to reduced reactor pressure and RFP NPSH limits uncontrolled RPV injection could occur if feedwater block valves RFW-V-65A(B) are not closed after a scram.

- 5.1 **PLACE** the startup level controller in MANUAL
- 5.2 **PLACE** the master level controller in AUTO
- 5.3 **OPEN** the startup control valve (startup level controller) <u>FULLY</u>
- 5.4 **OPEN** RFW-V-112A "RFW-HX-6A DISCHARGE TO REACTOR"
- 5.5 **MONITOR** RPV level to ensure RPV level is maintained.
- 5.6 **OPEN** RFW-V-112B "RFW-HX-6B DISCHARGE TO REACTOR"
- 5.7 **REPEAT** step 5.5
- 5.8 **CLOSE** RFW-V-118 "FEEDWATER STARTUP ISOLATION"
- 5.9 **REPEAT** step 5.5
- 5.10 **CLOSE** the startup control valve (startup level controller) <u>FULLY</u>